

## Attachment 1: Delete Level 4s

L4 id	req_key	rel	req_type	req_status	ver_method	ver_status	CCR	clarification	text
F-HRD-00085	-1040	A	functional	<u>approved</u>	inspection	<u>unverified</u>			The cabinet shall provide removable side panels and rear door.
F-HRD-02090	-1070	A	functional	<u>approved</u>	inspection	<u>unverified</u>			The cabinet shall provide removable side panels and rear door.

## Attachment 2: Modify Level 4 Text

L4 id	req_key	rel	req_type	req_status	ver_method	ver_status	CCR	clarification	text
F-HRD-01015	1046	A	functional	<u>approved</u>	inspection	<u>unverified</u>			Each User Station shall provide one color text and graphics display device which shall: a. Display the complete ASCII character set b. Provide a minimum of 1024 pixel x 864 lines resolution display c. Display a minimum of 16 colors d. Display pages 24 lines by 80 characters

L4 id	req_key	rel	req_type	req_status	ver_method	ver_status	CCR	clarification	text
									wide e. Display a minimum of four screen display pages f. Display pages readable from any location along the width of the workstation and up to a distance of 6 feet from the screen g. Provide a minimum of <del>17</del> <sup>19</sup> inches diagonal non-glare screen h. Provide RGB video output for hard copy i. Feature an integral swivel/tilt base j. Provide brightness, contrast and power controls within easy reach. k. Be physically relocatable within the operations center
F-HRD-02075	1067	A	functional	<u>approved</u>	inspection	<u>unverified</u>			The cabinet shall provide a minimum of

L4 id	req_key	rel	req_type	req_status	ver_method	ver_status	CCR	clarification	text
									3448 vertical Units (1 Unit = 1.75") of equipment mounting height.
F-HRD-03035	1079	A	functional	<u>approved</u>	demo	<u>unverified</u>			<u>Power supplies for the RAID shall be hot-swappable.</u> The following components shall be Hot Swappable: power supplies, fans, disk array controllers
F-HRD-03045	1081	A	performance	<u>approved</u>	inspection	<u>unverified</u>			The RAID unit shall have a data transfer rate of 1020MB per second.
F-HRD-06010	1094	A	functional	<u>approved</u>	test	<u>unverified</u>			The EOC shall be designed with system test features to enable checkout and test with minimum impact on operations, including test points, "T" connections, break-out boxes, and permanently installed test

**CCR: 97-0721**

**Baseline: 4/18/97**

**Query Date: 4/30/97**

L4 id	req_key	rel	req_type	req_status	ver_method	ver_status	CCR	clarification	text
									equipment.